SCHEDULE - B

Name of the Work: Construction of drain and culverts in Doddappaiah Layout in Ward No. 18

Indent No: 9986

Sl. No	Description of item	Unit	Qty	Rate (Rs)	
				In figures	In words
1	Earthwork excavation for foundation of buildings, Culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5m. In depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of clods complete as per specifications. P No.5 Ino 2.4 PWDSR - 2013-14	Cum	237.60	133.37	Rupees One Hundred Thirty Three And Paise Thirty Seven Only
2	Providing and laying in position plain cement concrete of mix M 7.5 with OPC cement @ 180 kgs using 40mm and down size graded granite metal CA @ 0.85 cum and FA @ 0.57 cum machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM machinery, curing complete as per specifications. Specification No.KBS 4. 1,4.2 P No. 12 I no 4.3 PWDSR - 2013-14	Cum	23.33	3771.66	Rupees Three Thousand Seven Hundred Seventy One And Paise Sixty Six Only
3	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications. specification No. KBS 4.6.2 P No 17. I No 4.31 PWDSR - 2013-14	Sqm	396.00	238.0	Rupees Two Hundred Thirty Eight Only
4	Providing an laying in position reinforced cement concrete of nominal mix M 20 with OPC @ 320 kgs with 20mm and down size graded granite metal, CA @ 0.878 cum and FA @ 0.459 cum and super palstisizer @ 3 ltr confirming to is 9103-1999 reaffirmed - 2008 machine mixed, concrete laid in layers not exceeding 15 cms thick, vibraited for all works in foundation plinth and ground floor level for retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, butresses, string or lacing courses, parapets, coping, bed blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. Specification No.KBS 4.1, 4.6 P No.13. I No. 4.11 PWDSR - 2013-14	Cum	50.90	4945.75	Rupees Four Thousand Nine Hundred Forty Five And Paise Seventy Five Only

Executive Engineer (Hubbal)

Sl. No	Description of item	Unit	Qty	Rate (Rs)	
				In figures	In words
5	Providing and fixing Pre cast solid concrete kerb stones made out of CC 1:2:4 and finished with CM 1:3 plastering and finishing cutting etc., complete. of size 450 x 200 x 400 mm P 24 I NO 5.29.1 PWDSR - 2013-14	Nos	188.00	278.15	Rupees Two Hundred Seventy Eight And Paise Fifteen Only
6	Providing TMT steel reinforcement for R.C.C work including straghtening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with bindig wire and anchoring to the adjining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per spedification No. KBS 4.6.3 Page No.19.I No.4.46 PWDSR - 2013-14	Qtl	30.54	6487.63	Rupees Six Thousand Four Hundred Eighty Seven And Paise Sixty Three Only
7	Providing and laying position reinforced cement concrete covering slabs madeout of mix 1:1.50:3 with 20mm and down size granite metal mixed concrete laid in layers not exceeding 15cms vibrated including cost of materials, labor curing providing and laying in position including transportation complete as per specification. (SLAB THICKNESS OF 10CMS)	Sqm	102.00	1254.46	Rupees One Thousand Two Hundred Fifty Four And Paise Forty Six Only
8	Conveying the excavated earth by private vehicle including loading and unloading charges up to 10 kms with all lead and lift.	Cum	220.00	83.34	Rupees Eighty Three And Paise Thirty Four Only
9	Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plasered concrete surfaces, with materials, labour compete as per specifications. Specification No.KRBS 800.3 MORT & H Specification No.800. P No. 195. I no 24.1 PWDSR - 2013-14	Sqm	25.50	45.56	Rupees Forty Five And Paise Fifty Six Only